



Finance & Facilities Management

Purchasing Department
Detroit, Michigan 48202
(313) 577-3734
FAX (313) 577-3747

August 25, 2008

**Addendum Number One To
Request for Quotation
5425 Woodward Mechanical Service Upgrade Re-bid WSU M-05097
dated, August 11, 2008**

Thank you for attending the University's pre-bid meeting regarding its Request for Quotation process 5425 Woodward Mechanical Service Upgrade Project # WSU M-05097 on August 18, 2008. We have prepared Addendum Number One (1) to the RFQ to provide the following important information:

Please Note, this addendum must be acknowledged in Section 300, Form of Proposal.

As a reminder, quotations are due by 2:00 p.m., August 28, 2008, at the University's Purchasing Department, located at:

Wayne State University
Purchasing Department, 4th Floor, Room #4200
5700 Cass Avenue
Detroit, MI 48202

Should you have any questions or concerns about this Addendum, please contact me at (313) 577-3757. Thank you for your interest in doing business with Wayne State University.

Thank you.

Kimberly Tomaszewski
Senior Buyer

ADDENDUM NO. 1

This Addendum is issued before award of the contract to inform Bidders of clarifications and/or revisions to the Bidding Documents.

The requirements contained in the Bidding documents shall apply to this Addendum. The general character of the Work called for in this Addendum shall be the same as originally set forth in the applicable portions of the bidding documents for similar work, unless otherwise specified under this Addendum. All incidental work necessitated by the Addendum as required to complete the work shall be included in the bids, even though not specifically mentioned in this Addendum.

This Addendum is hereby made a part of the Bidding Documents and shall be included in the Contract

DRAWINGS

Item -1: Replace the following sheets with current sheets available at University Purchasing Web-Site at: http://www.purchasing.wayne.edu/Adv_bid/Adv_bid.html

- M-2: Revised - existing ductwork from AHU-02 in the basement ceiling located outside the Mechanical Equipment Room to be left abandoned in place. Demolition of existing AHU-02 ductwork shall be confined only within the Mechanical Equipment Room
- M-3: Revised the chilled water piping layout to match the schematic piping diagram on sheet M-10.
- M-5 thru M-8: Reissued these sheets since the background had changed.
- M-10: Added design basis for thermal stability tank.
- M-12: Revised the fan schedule to eliminate the new roof exhaust fan EF-01. Existing fan serving the toilets to remain.
- E-1: Revised the note to read "Distribution Panel by others (This contractor shall provide all of the wiring to this panel and to equipment served by the panel)".

END OF ADDENDUM